ENGINEERING DEPARTMENT.

MYSORE DIVISION.

Notification dated 4th December 1925.

It is hereby notified for the information of the public, that sealed tenders may be submitted for the construction of Dispensary Building with out-houses at Bannur, T.-Narsipur Taluk, Mysore District, as per approved design.

The approximate quantities of work is given in the list attached.

2. The tenders should be enclosed in a sealed cover and superscribed "For Dispensary Building at Bannur" addressed to the Executive Engineer, Mysore Division, Mysore. Earnest money of Rs. 200 either in cash or in currency notes each of one hundred rupees value, should accompany the tender.

3. The last date up to which tenders can be received in the Executive Engineer's Office will be 22nd December 1925 (up to 12 noon) and after that date, no tenders will be received.

4. The right of acceptance of the tender or otherwise, rests with the Executive Engineer, Mysore Division, Mysore, and no reason will be assigned in the latter case.

5. The accepted tenderer will at once deposit in the Mysore District Treasury or at the T.-Narsipur Taluk Treasury, a further sum of Rs. 100 (one hundred) making a total of rupees three hundred only as a guarantee for the timely completion of the work and send in to this office, the treasury chellan in support of the latter amount.

6. The work (as a whole) should be completed before 31st October 1926.

7. The accepted tenderer should bind himself to give a written mutchalika on a stamped paper with conditions that may be stipulated by the Executive Engineer.

8. The approved plan of the building will be made available to the tenderers at the Executive Engineer's Office during working hours excepting on Sundays and authorized holidays.

Abstract estimate for constructing dispensary with out-houses at Bannur, T.-Narsipur Taluk.

No.	Items of work	Per	Rate	Quantity	Cost	Total
	DISPENSARY BUILDING.		Rs. a. p.		Rs.	Rs.
1	Earthwork excavation	C.yd.	0 4 0	67	17	..
2	Brick in mortar	C.ft.	0 4 6	4,962	1,300	..
3	Do arch work	,,	0 7 0	99	43	..
4	Burnt stone slabs 6" thick and dressed	S.ft.	0 10 6	411	257	..
5	Cut stone pillars and bases complete	each	28 0 0	10	280	..
6	Masonry moulding at ends	,,	5 0 0	2	10	..
7	Plastering with mortar	Sqr.	3 8 0	39·62	139	..
8	White washing	,,	0 4 0	23·39	6	..
9	Colour wasing	,,	0 6 0	16·43	6	..
10	Teakwood pannelled doors with hinges, etc., complete	S.ft.	2 0 0	126	252	..
11	Teakwood windows with iron bars of ½" dia. pannelled shutters.	,,	3 8 0	52	182	..
12	Teakwood glazed shutters	,,	4 0 0	30	120	..
13	Ventilators with glazed shutters	,,	2 0 0	27	54	..
14	Circular ventilators	,,	2 4 0	13	29	..
15	Teakwood wrought and put up	C.ft.	6 8 0	112·79	732	..
16	Roofing with first class Mangalore tiles over teak reepers, etc., complete.	Sqr.	35 0 0	19·31	676	..
17	Ridge tiles set in mortar and cement pointing	R.ft.	0 12 0	80	60	..
18	Zink sheet for valley	,,	0 12 0	44	33	..
19	Teakwood planks 1" thick	S.ft.	0 8 0	44	22	..
20	Eave board 9" high ornamental	R.ft.	0 12 0	202	197	..
21	Cornice 3" complete	,,	0 6 0	28	10	..
22	Wood oiling two coats	Sqr.	3 0 0	17·19	52	..
23	Chocolate painting	,,	5 0 0	8·79	44	..
24	Teakwood finials	each	5 0 0	4	20	..
25	Teakwook shelf planks 1½" thick	S.ft.	1 4 0	60	83	..
26	Flooring with 2" square Mangalore tiles over 3" concrete and cement pointing.	Sqr.	35 0 0	4·56	160	..
27	Flooring with Cadapa slabs over 3" concrete and cement pointing.	,,	35 0 0	4·85	170	..
28	Constructing cisterns.	each	5 0 0	2	10	..
29	Clearing silt	L. S.	Rs.	..	50	..
	Total ...	..	..	..	5,110	5,110
	KITCHEN.					
1	Earthwork excavation	C.yd.	0 4 0	4	1	..
2	Burnt brick in chunam	C.ft.	0 4 6	448	126	..
3	Burnt stone slabs 6" thick, dressed	S.ft.	0 10 0	23	14	..
4	Plastering with chunam	Sqr.	3 8 0	5·83	20	..
5	White and colour washing	,,	0 6 0	5·83	2	..
6	Teakwood battened door	S.ft.	1 8 0	18	27	..
7	Teakwood windows with iron bars, complete	,,	2 0 0	4½	0	..
8	Teakwood wrought and put up	C.ft.	6 8 0	8·01	52	..
9	Roofing with first class Mangalore tiles over teak reepers.	Sqr.	35 0 0	2·29	80	..

No.	Items of work	Per	Rate	Quantity	Cost	Total
			Rs. a. p.		Rs.	Rs.
10	Ridge tiles set in mortar	R.ft.	0 12 0	15	11	..
11	Teakwood plank eave board 6" high	"	0 8 0	60	30	..
12	Wood oiling, two coats	Sqr.	3 0 0	0·74	2	..
13	Chocolate painting	"	5 0 0	1·05	5	..
14	Flooring with Cadapa slabs over 3" concrete, etc. ..	"	35 0 0	0·70	25	..
15	Constructing over and cistern	L. S.	Rs.	..	5	..
16	Ventilating tiles for Kitchen	each	2 0 0	4	8	..
	Total —	..	..	..	417	417
	LATRINE.					
1	Earthwork excavating	C.yd.	0 4 0	4	1	..
2	Burnt brick in mortar	C.ft.	0 4 6	302	102	..
3	Coping with burnt brick in mortar and plastering ..	R.ft.	0 8 0	40	20	..
4	Plastering with mortar	Sqr.	3 8 0	4·26	15	..
7	Tarring	"	3 0 0	1·08	3	..
8	Flooring with Cadapa slabs over 3" concrete and cement pointing.	"	35 0 0	0·63	22	..
	Total cost of latrine ..	..	..	..	163	163
	Total for all the three ..	..	..	..	..	5,090
	Contingencies at 5 per cent ..	..	..	..	..	310
	Grand Total Rs. ..	..	..	..	..	6,000
	Compensation amount to be paid for acquiring lands for construction of dispensary.	..	..	..		300
	Total Rupees ..	..	..	..	.	6,300

K. R. GARUDACHAR,
For *Executive Engineer.*